



SCALE: NONE



- 1. RAMP AND APPROACHES SHALL BE CLEAR OF OBSTACLES INCLUDING HYDRANTS, POLES, AND INLETS.
- 2. RAMP SHALL HAVE DETECTABLE WARNING SURFACE PER WSDOT STANDARD PLAN F-45.10-01.
- 3. RAMP Q SHALL BE PERPENDICULAR TO OR RADIAL TO CURB RETURNS UNLESS OTHERWISE APPROVED BY THE PROJECT
- 4. WHERE REQUIRED BY THE JURISDICTIONAL AGENCY STANDARDS, PLACE A 4" WIDE VISUAL WARNING STRIP BETWEEN JOINTS OR SCORES.
- 5. REMOVAL OF EXISTING CURB RAMPS OR SIDEWALK FOR CONSTRUCTION OF NEW CURB RAMPS SHALL BE TO THE NEAREST JOINT. SAWCUT AT EXPANSION JOINT AS REQUIRED. REMOVE SIDEWALK AND CURB AND GUTTER AS REQUIRED TO OBTAIN ADEQUATE SPACING FOR NEW CURB RAMP TRANSITION AND WARNING STRIP(WHERE REQUIRED).
- 6. CURB RAMP LOCATION AND CONSTRUCTION ON ARTERIAL AND RESIDENTIAL STREETS SHALL BE IN ACCORDANCE WITH THE STANDARDS OF THE JURISDICTIONAL AGENCY.





KCMT 2021-2022 STANDARD DETAILS						
Δ						
\triangle						
\triangle						
\triangle						
No.	REVISION	BY	APP'D	DATE		



DESIGNED:	APPROVED:	
K. CHANG YUEN	P. ENG	
DRAWN:		
L. ANDERSON		
CHECKED:	PROJECT NO:	
K. CHANG YUEN	-	
CHECKED:	CONTRACT NO:	
C. ASQUITH	-	

King County METRO

METRO TRANSIT CAPITAL DIVISION TRANSIT PASSENGER FACILIITES - IMPROVEMENTS

> **CURB RAMP CONSTRUCTION DETAILS**

DATE:
05/2022
DRAWING NO:
D 4 4 0

D110 SHEET NO: OF

18 20